


KEVIN QUINN, PE

SCALE: 1"=30'



## **GENERAL NOTES:**

1. ALL REQUIRED PERMITS SHALL BE SECURED PRIOR TO COMMENCING WORK. PRIOR TO COMMENCING ANY WORK ONSITE, CONTRACTOR SHALL NOTIFY THE TOWN OF PAXTON PLANNING AND ENGINEERING DEPARTMENTS, BUILDING DEPARTMENT, CONSERVATION COMMISSION, DEPARTMENT OF PUBLIC WORKS, SCHOOL DEPARTMENT, POLICE AND FIRE DEPARTMENTS.

2. ALL WORK SHALL CONFORM TO THE TOWN OF PAXTON REGULATIONS. ZONING BY-LAW, CONSERVATION COMMISSION LOCAL BY-LAW OR OTHER REGULATIONS AS APPLICABLE. ALL REQUIREMENTS OF THE TOWN OF PAXTON ARE HEREBY MADE CONDITIONS OF THIS WORK. 3. CONTRACTOR SHALL CONTROL AIRBORNE DUST WITH USE OF SPRAYED WATER AS REQUIRED TO MINIMIZE IMPACT ON NEIGHBORING PROPERTIES. USE OF CALCIUM CHLORIDE OR OTHER CHEMICALS IS NOT PERMITTED.

4. CONTRACTOR SHALL RETAIN A LICENSED SURVEYOR TO LAY OUT THE SITE, WHO CERTIFY THAT ALL LOCATIONS ARE AS PER PLAN. 5. SEVENTY TWO HOURS PRIOR TO COMMENCING ANY EXCAVATION, THE CONTRACTOR SHALL NOTIFY DIG SAFE AT 811. THE CONTRACTOR SHALL COORDINATE NEW UTILITIES WITH THE VICINITY OF EXISTING UTILITIES (UNDERGROUND/OVERHEAD) WITH THE APPROPRIATE UTILITY. 6. INTERIM AND/OR PERMANENT SOIL STABILIZATION MEASURE SHALL BE INSTITUTED AS SOON AS PRACTICABLE, BUT NO MORE THAN 14

DAYS AFTER CONSTRUCTION ACTIVITY HAS TEMPORARILY OR PERMANENTLY CEASED ON THAT PORTION OF THE SITE. 7. REMOVE ALL TOPSOIL, SUBSOIL, PRIOR TO PLACING ANY FILL ONSITE. WHERE GRAVEL IS CALLED FOR ONSITE, CONTRACTOR MAY UTILIZE ONSITE MATERIALS, IF APPROVED BY OWNER.

8. CONTRACTOR SHALL MAINTAIN COMPLETE RECORDS OF AS-BUILT LOCATIONS OF ALL UNDERGROUND AND ABOVE GROUND FACILITIES. PROVIDE THE OWNER WITH COMPLETE AS-BUILT PLANS UPON COMPLETION OF PROJECT, INCLUDING UTILITIES NOT INDICATED ON THIS PLAN. 9. CONSTRUCTION SEQUENCE: ALL WORK OF THIS PROJECT SHALL PROCEED ACCORDING TO THE FOLLOWING PROPOSED SEQUENCE: 1.) EROSION CONTROL PROVISIONS IN PLACE AND INSPECTED BY TOWN

- 2.) CLEARING/GRUBBING OF SITE DRIVEWAY/WETLAND CROSSING (SEE WETLAND REPLICATION PROTOCOLS BELOW FOR ADDITIONAL DETAIL) 3.) CONSTRUCT AND STABILIZE FRONT DRIVEWAY SWALE AND ROUGH IN PROPOSED DRIVEWAY UP TO WETLAND CROSSING
- 4.) GRADE AREAS AT WETLAND CROSSING, INSTALL OPEN BOTTOM CULVERTS AND RETAINING WALLS, AND BRING TO PROPOSED GRADE
- 5.) CONSTRUCT WETLAND REPLICATION AREAS (FINAL PLANTING AND STABILIZATION TO OCCUR EARLY OR LATE SEASON)
- 6.) CONSTRUCT AND STABILIZE DRAINAGE SWALES AFTER WETLAND CROSSING AND ROUGH IN REMAINDER OF DRIVEWAY 7.) ROUGH GRADE REMAINDER OF SITE, HOUSE AND SEPTIC SYSTEM CONSTRUCTION

8.) FINAL SITE STABILIZATION AND EROSION CONTROL REMOVAL (REMOVE EC'S AFTER APPROVAL FROM TOWN BOARDS) 10. CONTRACTOR SHALL PLACE A MINIMUM OF 6" (COMPACTED DEPTH) OF GOOD QUALITY LOAM AND GRASS SEED IN ALL AREAS NOT SUBJECT TO RESTORATION BY ANY OTHER MEANS.

11. THE CONTRACTOR SHALL BE RESPONSIBLE TO COORDINATE HIS WORK WITH MUNICIPALITY TO LIMIT THE POTENTIAL DISRUPTIONS TO THE THE GENERAL PUBLIC. SHALL EMPLOY DUE CARE AND CAUTION TO PROTECT THE PUBLIC FROM DANGERS ASSOCIATED WITH THE OPERATION. SHALL INSTALL TEMPORARY FENCES, BARRICADES AND SIGNAGE TO ENSURE THAT NO PERSONS ENTER THE WORK AREA. SHALL COORDINATE 13. THE FOLLOWING PAVEMENT SWEEPING SCHEDULE IS RECOMMENDED WITH SWEEPING SCHEDULED PRIMARILY IN THE POLICE DETAILS AS REQUIRED FOR WORK TO BE CONDUCTED IN THE STREET. SHALL EMPLOY DUE CARE WHEN WORKING AROUND PEDESTRIAN AND VEHICLE TRAFFIC.

12. NO EXCAVATION SHALL TAKE PLACE ONSITE UNTIL ALL SEDIMENTATION CONTROLS (STRAW WATTLES, TEMP BASINS, ETC.) ARE FULLY INSTALLED AS PER PLAN. FOLLOWING COMPLETION OF GRADING IN ANY AREA CONTRACTOR SHALL ACT TO PLACE PERMANENT SURFACE FINISH OR TO STABILIZE SURFACE SOILS AGAINST EROSION. LOAM AND SEED SHALL BE PLACED IMMEDIATELY UPON FINAL GRADING. 13. THE CONTRACTOR SHALL BE RESPONSIBLE TO ENSURE THAT THE CONSTRUCTION ACTIVITIES DO NOT DAMAGE OR UNDERMINE EXISTING SLOPES, BUILDINGS, WALLS, STRUCTURES, ETC. IN THE AREA AROUND THE CONSTRUCTION. REPAIR OF EXISTING SLOPES, BUILDINGS, WALLS, 15. PARTIES RESPONSIBLE FOR MAINTENANCE OF THE STORMWATER SYSTEM SHOULD BECOME FAMILIAR WITH THE STRUCTURES, ETC. THAT ARE DAMAGED OR UNDERMINED BY THE CONTRACTORS WORK SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. REQUIREMENTS OF: 14. EXISTING UTILITY LOCATIONS ARE APPROXIMATE ARE TO BE FIELD VERIFIED. QUINN ENGINEERING, INC. DOES NOT WARRANT THAT ALL EXISTING UTILITIES HAVE BEEN INDICATED. THE CONTRACTOR IS RESPONSIBLE FOR COORDINATING THE EXISTING UTILITY LOCATIONS AND

ENSURING THAT THE PROPOSED WORK DOES NOT CONFLICT WITH THE EXISTING UTILITIES NOT SHOWN. 15. SEWERS SHOULD BE LAID AT A MINIMUM OF 10 FEET, HORIZONTALLY, FROM ANY EXISTING OR PROPOSED WATER MAIN. SHOULD LOCAL CONDITIONS PREVENT LATERAL SEPARATION OF 10 FEET TO A WATER MAIN, THE WATER MAIN SHOULD BE LAID IN A SEPARATE TRENCH AND THE ELEVATION OF THE CROWN OF THE SEWER PLACED AT LEAST 18 INCHES BELOW THE INVERT OF THE WATER MAIN. WHENEVER SEWERS MUST CROSS UNDER WATER MAINS, THE SEWER SHOULD BE LAID AT SUCH AN ELEVATION THAT THE CROWN OF THE SEWER IS AT LEAST 18 INCHES BELOW THE INVERT OF THE WATER MAIN. WHEN THE ELEVATION OF THE SEWER CAN NOT BE VARIED TO MEET THIS REQUIREMENT, THE WATER MAIN SHOULD BE RELOCATED TO PROVIDE THIS SEPARATION OR CONSTRUCTED WITH MECHANICAL-JOINT PIPE FOR A DISTANCE OF 10 FEET ON EACH SIDE OF THE SEWER. ONE FULL LENGTH OF WATER MAIN SHOULD BE CENTERED OVER THE SEWER SO THAT BOTH JOINTS WILL BE AS FAR FROM THE SEWER AS POSSIBLE. WHEN IT IS IMPOSSIBLE TO OBTAIN HORIZONTAL OR VERTICAL SEPARATION AS STIPULATED ABOVE, BOTH SEWER AND WATER MAIN SHOULD BE ENCASED IN CONCRETE FOR 10 FEET EITHER SIDE OF THE CROSSING.

16. THE GROUND IMMEDIATELY ADJACENT TO FOUNDATIONS SHALL BE SLOPED AWAY FROM THE BUILDING, IN ACCORDANCE WITH 780 CMR 1813.7. AT A SLOPE OF NOT LESS THAN 1:12 FOR A MINIMUM DISTANCE OF 10 FEET MEASURED PERPENDICULAR TO THE FACE OF THE WALL. OTHER APPROVED ALTERNATE METHODS OF DIVERTING WATER AWAY FROM THE FOUNDATION MAY BE ACCEPTABLE. 17. ALL SDR35 PVC SEWER PIPE & FITTINGS SHALL CONFORM TO ASTM D3034 OR ASTM F679.

18. ALL SCH. 40 & SCH. 80 PVC PIPE & FITTINGS SHALL CONFORM TO ASTM D178M D3915, .4, ASTM . D1785, ASTM D3915, ASTM D4396 19. THE SITE IS NOT LOCATED WITHIN A TOWN OF PAXTON WATERSHED RESOURCE PROTECTION DISTRICT.

20. SUITABLE FILL SHALL CONSIST OF MATERIAL SOIL FREE OF ORGANIC MATERIALS, LOAM, AND ANY DELETERIOUS MATERIALS. SUITABLE CONFORMABLE FILL SHALL NOT CONTAIN STONES LARGER THAN 10" IN ANY DIMENSION, AND SHALL HAVE LESS THAN 75% PASSING THE NO. 4 SIEVE AND A MAXIMUM OF 20% PASSING THE NO. 200 SIEVE. SUITABLE FILL SHALL NOT CONTAIN ANY BUILDING RUBBLE, GRANITE, 5. FOLLOWING COMPLETION OF GRADING IN ANY AREA, CONTRACTOR SHALL ACT TO PLACE PERMANENT SURFACE FINISH OR CONCRETE BLOCK, ROOFING MATERIALS, OR OTHER CONSTRUCTION REFUSE. AT THE TIME OF PLACEMENT SUITABLE FILL SHALL NOT OR TO STABILIZE SOILS AGAINST EROSION. LOAM AND SEED SHALL BE PLACED IMMEDIATELY UPON FINAL GRADING. CONTAIN FROST, SNOW, OR ICE AND SHALL NOT CONTAIN WATER GREATER THAN THE OPTIMAL MOISTURE CONTENT.

21. THE EROSION CONTROL LINE SHALL BE STAKED BY A MA REGISTERED SURVEYOR PRIOR TO THE INSTALLATION OF EROSION CONTROLS. 6. ALL EROSION CONTROL DEVICES SHALL BE MAINTAINED THROUGHOUT CONSTRUCTION AND SHALL NOT BE REMOVED THE EROSION CONTROL LINE SHALL SERVE AS THE LIMIT OF WORK. 22. SITE OPERATIONS SHALL NOT DIRECT HAZARDOUS MATERIALS IN QUANTITIES SUBSTANTIALLY GREATER THAT THOSE ASSOCIATE WITH

NORMAL HOUSEHOLD USE TO THE SOIL ABSORPTION SYSTEM. 23. RETAINING WALL SHALL BE VERSA-LOK PRECAST CONCRETE BLOCK RETAINING WALL SYSTEM, OR EQUAL. INSTALL WALL AS PER

MANUFACTURER'S RECOMMENDATIONS AND REQUIREMENTS. RETAINING WALLS WITH DIFFERENCES IN GRADE LEVEL ON EITHER SIDE OF THE 8. THE SITE DOES NOT LIE WITHIN A FLOOD HAZARD ZONE AS INDICATED ON NFIP FIRM MAPS. WALL IN EXCESS OF FOUR FEET SHALL BE DESIGNED BY A MASSACHUSETTS REGISTERED PROFESSIONAL STRUCTURAL ENGINEER IN ACCORDANCE WITH 780 CMR 116.0. THE MA REGISTERED PROFESSIONAL STRUCTURAL ENGINEER SHALL PROVIDE HIS/HER SEAL AND SIGNATURE ON THE CONSTRUCTION PLANS AND SPECIFICATIONS. RETAINING WALLS WITH DIFFERENCES IN GRADE LEVEL ON EITHER SIDE OF THE WALL IN EXCESS OF FOUR FEET, ARE CLOSER THAN TWO FEET TO A WALK, PATH, PARKING LOT, OR DRIVEWAY ON THE HIGH SIDE SHALL BE PROVIDED WITH GUARDS THAT ARE CONSTRUCTED IN ACCORDANCE WITH 780 CMR 1021.0. INTEGRITY OF THE WALL.

WETLAND & STREAM REPLICATION/RESTORATION PROTOCOL

THE SITE PLANS DEPICT THE RE-CONSTRUCTION OF THE STREAM CHANNEL WITH A CROSS-SECTIONAL DETAIL.

- THE WETLAND BOUNDARIES (I.E., DOWNGRADIENT EDGES OF THE WETLAND REPLICATION AREA) WILL BE MARKED IN THE FIELD. PRIOR TO THE START OF EARTH-MOVING ACTIVITIES IN THE REPLICATION AREA, AN EROSION CONTROL BARRIER OF PROPERLY INSTALLED SILTATION FENCE (I.E., THE BOTTOM FEW INCHES OF THE SILTATION FENCE INSTALLED IN A NARROW, TRENCH AND THE TRENCH FILLED WITH SOIL AROUND THE SILTATION FENCE) WILL BE INSTALLED ALONG THE WETLAND BOUNDARIES BETWEEN THE WETLAND AND THE WETLAND REPLICATION AREA. THE PROJECT WETLAND SCIENTIST WILL EVALUATE THE REPLICATION AREA PRIOR TO CLEARING AND DETERMINE IF ANY EXISTING TREES CAN BE SAVED. THE WETLAND REPLICATION AREA WILL THEN BE CLEARED AND GRUBBED. WITH THE EXCEPTION OF ANY TREES THAT HAVE BEEN MARKED TO BE SAVED. 3. THE PROPOSED FINAL GRADE FOR THE REPLICATION AREA SHOULD APPROXIMATE THE ELEVATION OF THE ADJACENT WETLAND AREAS, AS NOTED ON THE SITE PLANS. THE REPLICATION AREA WILL BE EXCAVATED TO A DEPTH OF 12-INCHES BELOW THE PROPOSED
- HYDROLOGIC CONDITIONS. ALL EXCAVATED MATERIAL WILL BE DISPOSED OF AWAY FROM ALL WETLAND RESOURCE AREAS AND PROTECTED FROM EROSION. ROCK PILES WILL BE PLACED AT SUB-GRADE AS NOTED AT ITEM NO. 7 BELOW. . EXISTING TOPSOILS WITHIN THE IMPACT AREA WILL BE EXCAVATED, STOCKPILED AND MOVED IMMEDIATELY TO THE PREPARED REPLICATION AREA OR KEPT MOIST BY WATERING AND/OR COVERING. 5. RELOCATED WETLAND TOPSOILS WILL BE SUPPLEMENTED WITH A 1:1 MIXTURE OF HIGH QUALITY. LOAMY TOPSOIL AND LEAF MULCH COMPOST. AS NECESSARY. TO APPROXIMATE 12-INCHES IN THICKNESS THROUGHOUT THE REPLICATION AREA. THE SUBSTRATE WILL BE ROUGHLY GRADED TO PROVIDE AN APPROPRIATE MICROTOPOGRAPHY. A MINIMUM OF 4 INCHES OF LOAMY TOPSOIL WILL BE APPLIED TO THE SIDE-SLOPES OF THE WETLAND REPLICATION AREA. THE SIDE SLOPES SHOULD BE STABILIZED AS NECESSARY TO PREVENT
- EROSION 6. WILDLIFE ENHANCEMENT MEASURES INCLUDING THREE (3) TREE SNAGS AND ONE (1) ROCK PILE WILL BE INSTALLED WITHIN EACH REPLICATION AREA. THE TREE SNAGS WILL CONSIST OF 10 TO 15 FOOT LOGS PLACED RANDOMLY ON THE FINISHED SURFACE. THE TREE SNAGS WILL PROVIDE FOOD, FORAGE AND CAVITY NESTING OPPORTUNITIES. THE ROCK PILES WILL CONSIST OF FIVE OR SIX BOULDERS EACH (APPROXIMATELY 24 INCHES IN DIAMETER) PILED AT SUB-GRADE SO AS TO CREATE CREVICES AND CAVITIES FOR SHELTER AND NESTING
- AN EROSION CONTROL BARRIER COMPRISING ONLY TOED-IN SILTATION FENCE WILL BE PROPERLY INSTALLED BETWEEN THE COMPLETED REPLICATION AREA AND THE ADJACENT UPLAND SIDESLOPES. B. PLANTING WILL BE DONE ONLY DURING THE BEGINNING (APRIL 15 THROUGH JUNE 1) OR END (SEPTEMBER 15 TO NOVEMBER 1) OF THE GROWING SEASON. PLANTING IN THE MID-GROWING SEASON IS ONLY ACCEPTABLE IF IRRIGATION IS PROVIDED. THE NATIVE PLANT SPECIES IDENTIFIED IN THE TABLES BELOW WILL BE PLANTED IN THE REPLICATION AREA EITHER BY TRANSPLANT OR FROM NURSERY STOCK. THE SAPLINGS WILL BE DISTRIBUTED THROUGHOUT THE AREA. THE SHRUBS WILL BE PLANTED RANDOMLY THROUGHOUT THE AREA IN CLUMPS OF TWO TO THREE WITH THE AVERAGE SPACING BETWEEN SHRUB CLUMPS APPROXIMATELY 5 FEET ON-CENTER. THE WOODY VEGETATION SHOULD NOT BE PLANTED IN ROWS. THE HERBACEOUS SPECIES WILL BE PLANTED BETWEEN THE SHRUBS AND SAPLINGS

### PLANTING PLAN FOR EACH OF THREE (3), 600 S.F. WETLAND REPLICATION AREAS

### SPECIES; SIZE; SPACING; NUMBER

SAPLINGS; 6' TO 8' HEIGHT, CONTAINER OR BALLED, BURLAPPED; 15' ON-CENTER AVG. RED MAPLE (ACER RUBRUM) 2

YELLOW BIRCH (BETULA ALLEGHENIENSIS) 1

SHRUBS; 2.5' TO 3' IN HEIGHT, CONTAINER; 5' ON-CENTER AVERAGE SPACING HIGHBUSH BLUEBERRY (VACCINIUM CORYMBOSUM) 12

WINTERBERRY (ILEX VERTICILLATA) 12

HERBACEOUS; CONTAINERIZED; 5' ON-CENTER AVERAGE SPACING

CINNAMON FERN (OSMUNDA CINNAMOMEA) 24

9. THE PLANTED REPLICATION AREA WILL BE MULCHED WITH 1 TO 2 INCHES OF SHREDDED LEAVES OR WEED-FREE STRAW TO SIMULATE A FOREST FLOOR AND TO PROVIDE FOR TEMPORARY EROSION CONTROL AND MOISTURE RETENTION. 10. THE SIDE-SLOPES OF THE WETLAND REPLICATION AREA WILL BE SEEDED WITH A NATIVE GRASS/WILDFLOWER MIXTURE DESIGNED TO PROVIDE PERMANENT COVER. AFTER SEEDING, THE SIDE-SLOPES WILL BE MULCHED WITH A THIN LAYER OF WEED-FREE STRAW TO PROVIDE FOR TEMPORARY EROSION CONTROL

ESTABLISHED. IF INVASIVE SPECIES ARE NOTED (E.G., KNOTWEED, PHRAGMITES, ETC.) THESE SPECIES WILL BE REMOVED BY EITHER HAND-PULLING THE ENTIRE PLANT OUT BY THE ROOTS OR BY CUTTING THE ABOVE-GROUND PORTION AND APPLYING GLYPHOSATE HERBICIDE TO THE STEM WITH A DRIP APPLICATOR. THE CUT OR PULLED PLANTS WILL BE PROPERLY DISPOSED OF OUTSIDE THE WETLANDS AND BUFFER ZONES AND CARE WILL BE TAKEN NOT TO DISTRIBUTE ANY SEEDS OR BERRIES THAT MAY BE PRESENT. 12. AFTER THE WETLAND REPLICATION AREA HAS BECOME VEGETATIVELY STABILIZED, AND FOLLOWING APPROVAL OF THE ISSUING AUTHORITY, THE SILTATION FENCE AND ALL WOODEN STAKES WILL BE REMOVED AND DISPOSED OF PROPERLY. 13. IMPACTS TO STREAM BANKS AND LAND UNDER WATER, AT THE PROPOSED WETLAND CROSSING, WILL BE MITIGATED THROUGH THE USE OF AN OPEN-BOTTOM BOX CULVERT "SPANS" AND RESTORATION OF THE STREAM CHANNELS WITHIN THE BOX CULVERT. THE STREAMS WILL BE RESTORED AS FOLLOWS:

WORK WITHIN THE STREAM WILL ONLY BE CONDUCTED DURING A LOW-FLOW OR NO-FLOW PERIOD, TYPICALLY BETWEEN JULY 1 AND SEPTEMBER 30. WORK OUTSIDE THIS TIME PERIOD MAY BE DONE WITH APPROVAL FROM THE CONSERVATION COMMISSION OR THEIR DESIGNATED AGENT. PROVISIONS MUST BE IN PLACE TO RE-DIRECT OR PUMP ANY STREAM FLOW AROUND OR THROUGH THE WORK AREA WITHOUT EXPOSURE TO SEDIMENT OR OTHER CONTAMINANTS. DE-WATERING OF ANY GROUNDWATER WILL BE DONE USING PUMPS WITH PROPERLY FILTERED DISCHARGE LOCATED OUTSIDE THE WETLAND. THE STREAM CHANNEL WILL BE GRADED IN A SINUOUS CONFIGURATION TO MATCH THE PROFILES OF THE EXISTING STREAM ON EITHER SIDE OF THE CROSSING.

THE RE-CONSTRUCTED STREAM CHANNEL WILL BE LINED WITH BIODEGRADABLE COIR OR JUTE FABRIC THAT IS KEYED INTO THE NATIVE TOPSOIL ABOVE THE STREAM BANKS. STAKED AND TIED, BIODEGRADABLE FIBER LOGS (MINIMUM 8-INCH DIAMETER) WILL BE PLACED OVER THE FABRIC TO FORM THE STREAM BANKS. THE NATIVE TOPSOIL HAS BEEN STRIPPED IT WILL BE REPLACED WITH 6 INCHES OF UNSCREENED, ON-SITE TOPSOIL/LOAM. NATIVE OR RESTORED SOILS ABOVE THE BANKS WILL BE MULCHED WITH 1 TO 2 INCHES OF BARK OR CHOPPED LEAVES. GRAVEL AND ROUNDED COBBLES (6-INCH MINUS) WILL BE PLACED IN THE STREAM BED TO APPROXIMATE THE EXISTING STREAM BED ABOVE AND BELOW THE CROSSING.

### LONG TERM POLLUTION PREVENTION PLAN MEASURES: CONSTRUCTION PERIOD POLLUTION PREVENTION PLAN NOTES: PAXTON STORMWATER CREDITS:

- I. GOOD HOUSEKEEPING PRACTICES SHALL BE EMPLOYED IN MAINTENANCE OF THE STORMWATER SYSTEM AND ON SITE AREAS. THE MINIMUM HOUSEKEEPING PRACTICES ARE IDENTIFIED IN THE STORMWATER COLLECTION AND TREATMENT SYSTEM OPERATION AND MAINTENANCE PLAN.
- 2. STORAGE OF MATERIALS AND WASTE PRODUCTS SHALL BE STORED IN A MANNER THAT MINIMIZES EXPOSURE TO STORMWATER, IE USE OF TARPAULINS, INSIDE STORAGE, ETC. MATERIALS AND WASTE SHALL BE MAINTAINED IN AN ORDERLY MANNER AND SHALL BE COLLECTED IMMEDIATELY UPON SPILLS OR DISPERSION. 3. VEHICLE WASHING SHOULD OCCUR IN ACCORDANCE WITH THE "ILLICIT AND NON STORMWATER DISCHARGES'
- PORTION OF THE STORMWATER POLLUTION PREVENTION PLAN NOTES. 4. LONG TERM MAINTENANCE OF THE STORMWATER SYSTEM SHALL FOLLOW THE OPERATION AND MAINTENANCE REQUIREMENTS ON THESE PLANS AT A MINIMUM.
- 5. PARTIES RESPONSIBLE FOR MAINTENANCE OF THE STORMWATER SYSTEM SHOULD BE FAMILIAR WITH "CLEAN UP OF SITES AND SPILLS" INFORMATION AVAILABLE ON THE MA DEP WEB SITE (CURRENTLY AVAILABLE AT http://www.mass.gov/dep/cleanup/laws/spillmgm.doc) AND SHOULD BE PREPARED TO ACT ACCORDINGLY IN THE
- EVENT OF A SPILL. 6. THE MINIMUM PRACTICES EMPLOYED IN INSPECTION AND MAINTENANCE OF THE ON SITE AREAS AND STORMWATER SYSTEM COMPONENTS ARE IDENTIFIED IN THE STORMWATER COLLECTION AND TREATMENT SYSTEM OPERATION AND MAINTENANCE PLAN.
- 7. THE MASSACHUSETTS BUREAU OF FARM PRODUCTS & PLANT INDUSTRIES FACT SHEET FOR "PROTECTING WATER RESOURCES FROM FERTILIZER" RECOMMENDS THAT: UNUSED FERTILIZER SHOULD BE REMOVED FROM THE SPREADER AND RETURNED TO THE ORIGINAL BAG OR CONTAINER FOR FUTURE USE. STORE UNUSED FERTILIZER IN A DRY PLACE AWAY FROM ANY WATER SOURCE.
- F STORED FERTILIZER GETS WET YOU NOT ONLY LOSE NUTRIENT VALUE, THERE IS POTENTIAL FOR NITRATES TO LEACH INTO WATER SOURCES. THE HANDLING OF HERBICIDES AND PESTICIDES SHOULD BE CONDUCTED IN ACCORDANCE WITH GUIDELINES AVAILABLE ON THE MA DEP WEB SITE (CURRENTLY AVAILABLE AT http://www.mass.gov/dep/recycle/hazardous/pesticid.htm) 8. MANAGEMENT OF PET WASTE SHOULD BE CONDUCTED IN ACCORDANCE WITH THE GUIDELINES AVAILABLE ON THE MA DEP WEB SITE (CURRENTLY AVAILABLE AT http://www.mass.gov/dep/water/resources/petwaste.pdf) 9. OPERATION AND MAINTENANCE OF ANY ON SITE SEPTIC SYSTEM SHOULD BE CONDUCTED IN ACCORDANCE 310
- CMR 15.00. 10. SOLID WASTE SHOULD BE MANAGED IN ACCORDANCE WITH LOCAL, STATE, FEDERAL REGULATIONS AND
- GUIDELINES. 11. SNOW DISPOSAL SHALL BE CONDUCTED IN ACCORDANCE WITH THE MA DEP GUIDELINE BRPG01-01 (CURRENTLY
- AVAILABLE AT http://www.mass.gov/dep/water/laws/snowdisp.htm) 12. USE OF SALT ON ROADS AND WALKS IS TO BE MINIMIZED. STORAGE OF SNOW SALT AND OTHER DE-ICING MATERIALS SHALL BE IN ACCORDANCE WITH MA DEP POLICY DWSG97-1 (CURRENTLY AVAILABLE AT SPRING AND FALL
- QUARTERLY AVERAGE USING A HIGH EFFICIENCY VACUUM SWEEPER - QUARTERLY AVERAGE USING A REGENERATIVE AIR SWEEPER - MONTHLY AVERAGE USING A MECHANICAL SWEEPER (ROTARY BROOM) SWEEPINGS SHOULD BE HANDLED IN ACCORDANCE WITH MA DEP POLICY #BRP-94-092. 13. ILLICIT DISCHARGES TO THE STORMWATER SYSTEM ARE PROHIBITED. 14. FOR LAND USES NEAR CRITICAL AREAS OR FROM LAND USED WITH HIGHER POTENTIAL POLLUTANT LOADS THE STORMWATER SYSTEM SHOULD BE PROVIDED WITH A SHUTDOWN DEVICE.
- THE STORMWATER POLLUTION PREVENTION PLAN AND NOTES THE STORMWATER COLLECTION AND TREATMENT SYSTEM OPERATION AND MAINTENANCE PLAN - THESE LONG TERM POLLUTION PREVENTION PLAN MEASURES
- 16. IN THE CASE OF AN EMERGENCY DIAL 911 OR CONTACT: MASS DEP CENTRAL REGION 8 NEW BOND STREET WORCESTER, MA 01606
- (508) 792-7650

## WETLAND/STORMWATER NOTES:

1. WETLAND DELINEATION BY ECOTEC, INC., OF WORCESTER MA.

REPRESENTATIVE PRIOR TO STARTING CONSTRUCTION. 3. APPROVAL FROM THE PAXTON CONSERVATION COMMISSION IS REQUIRED FOR THIS PROJECT. WETLAND AREAS IDENTIFIED IN THIS PLAN SET QUALIFY AS WETLANDS UNDER 310 CMR 10.00.

# FULLY INSTALLED PER PLAN.

UNTIL ALL DISTURBED SURFACES HAVE BEEN FULLY STABILIZED WITH VEGETATION.

- 7. EXISTING ROADS CONNECTED TO THE PROJECT SITE WILL BE KEPT CLEAN OF SILT AND DEBRIS AT ALL TIMES.
- 9. THE SITE DOES LIE WITHIN A ZONE A WATER SUPPLY PROTECTION AREA AS MAPPED ON THE MASS GIS WEBSITE.
- 10. THE SITE DOES NOT LIE WITHIN AN ESTIMATED HABITAT OR RARE WILDLIFE OR PRIORITY HABITAT OF RARE SPECIES.

PLANTING PLAN FOR 200 S.F. WETLAND REPLICATION AREA SPECIES; SIZE; SPACING; NUMBER

SHRUBS; 2.5 TO 3' IN HEIGHT, CONTAINER; 5' ON-CENTER AVERAGE SPACING HIGHBUSH BLUEBERRY (VACCINIUM CORYMBOSUM) 4

WINTERBERRY (ILEX VERTICILLATA) 4 HERBACEOUS; CONTAINERIZED; 5' ON-CENTER AVERAGE SPACING

CINNAMON FERN (OSMUNDA CINNAMOMEA) 8

RED MAPLE (ACER RUBRUM)


- 2. EROSION CONTROLS INCLUDING TEMPORARY BASINS SHALL BE IMPLEMENTED AND INSPECTED BY A TOWN

### 4. NO EXCAVATION SHALL TAKE PLACE ONSITE UNTIL ALL SEDIMENTATION CONTROLS (WATTLES, SILT FENCE, ETC.) ARE

- 11. IN NO CASE SHALL ANY WORK OCCUR BEYOND THE DEFINED LIMIT OF WORK/EROSION CONTROL LINES.
- FINAL GRADE. THE EXCAVATION AND PLANTING WORK WILL BE CLOSELY SUPERVISED BY A QUALIFIED WETLAND SCIENTIST. MODIFICATIONS TO THE PROPOSED GRADING MAY BE MADE IN THE FIELD BY THE WETLAND SCIENTIST IN RESPONSE TO OBSERVED SUBSURFACE

- SAPLINGS; 6 TO 8' HEIGHT, CONTAINER OR BALLED, BURLAPPED; 15' ON-CENTER AVG.
- 11. THE REPLICATION AREAS WILL BE INSPECTED, BY A QUALIFIED WETLAND SCIENTIST, AT THE END OF EACH GROWING SEASON FOR A MINIMUM OF TWO YEARS OR UNTIL SUCH TIME AS THE REQUIRED 75% OF VEGETATIVE COVER WITH WETLAND SPECIES HAS BEEN

- 1. CONTROLS TO REDUCE POLLUTANTS: A.) THE FOLLOWING IS A BRIEF DESCRIPTION OF EACH BMP IMPLEMENTED TO CONTROL POLLUTANTS IN STORM WATER DISCHARGES. 1.) EROSION CONTROLS: STRAW WATTLES PROVIDE MEASURES OF CONTROLLING EROSION AND SEDIMENTATION AND SHALL BE IMPLEMENTED BY THE CONTRACTOR WHERE NEEDED TO PREVENT SEDIMENT FROM LEAVING THE WORK SITE. 2.) EARTH DIKES, TEMPORARY DRAINAGE SWALES, INTERCEPTOR DIKES AND/OR SWALES SHALL BE EMPLOYED BY THE SITE CONTRACTOR TO DIRECT STORMWATER RUNOFF FROM DISTURBED AREAS TO AREAS WHERE DISCHARGE IS ACCEPTABLE.
- 3.) TEMPORARY CONSTRUCTION ENTRANCES OF CRUSHED STONE SHALL BE IMPLEMENTED BY THE CONTRACTOR WHEN NEEDED TO PREVENT SEDIMENT FROM TRACKING OFF-SITE AND INTO EXISTING ROADWAYS. B.) DISTURBED AREAS NOT SUBJECT TO RESTORATION BY OTHER MEANS SHALL BE STABILIZED UPON FINISH GRADING WITH 4" OF LOAM AND GRASS SEED. AREAS SLOPED AT GREATER THAN 3:1 SHALL BE STABILIZED WITH GEOTEXTILE FABRIC.
- C.) THE FOLLOWING RECORDS SHOULD BE MAINTAINED BY THE OPERATOR AS PART OF THE POLLUTION PREVENTION PLAN. 1. DATES WHEN MAJOR GRADING ACTIVITIES OCCUR. 2. DATES WHEN CONSTRUCTION ACTIVITIES TEMPORARILY OR PERMANENTLY CEASE ON A PORTION OF THE SITE.
- 3. DATES WHEN STABILIZATION MEASURES ARE INITIATED. D.) HAY BALES, SILT FENCE, STONE CONSTRUCTION ENTRANCES, EARTH DIKES, TEMPORARY DRAINAGE SWALES, INTERCEPTOR DIKES AND SWALES, AND OTHER STRUCTURAL PRACTICES SHALL BE EMPLOYED BY THE SITE CONTRACTOR TO DIRECT STORMWATER RUNOFF FROM DISTURBED AREAS TO AREAS WHERE DISCHARGE IS ACCEPTABLE. THE APPROPRIATE LOCATION AND INSTALLATION TIMING SHALL
- BE DETERMINED BY THE SITE CONTRACTOR. E.) THE DISCHARGE OF SOLID MATERIALS, INCLUDING BUILDING MATERIALS, TO ANY WETLAND AREAS, CATCH BASIN, STORMWATER BASIN, ETC. ARE PROHIBITED
- F.) THE CONTRACTOR SHALL MINIMIZE VEHICLE TRACKED SEDIMENT ONTO THE SURROUNDING ROADWAYS. AIRBORNE DUST SHALL BE CONTROLLED WITH WATER. G.) CONSTRUCTION MATERIALS AND CONSTRUCTION WASTE MATERIALS ASSOCIATED WITH THE PROPOSED DEVELOPMENT
- SHALL BE STORED IN A MANNER THAT MINIMIZES EXPOSURE TO STORMWATER, IE USE OF TARPAULINS, INSIDE STORAGE, ETC. MATERIALS AND WASTE SHALL BE MAINTAINED IN AN ORDERLY MANNER AND SHALL BE COLLECTED IMMEDIATELY UPON SPILLS OR DISPERSION.
- H.) DURING CONSTRUCTION, POLLUTANTS FROM SOURCES OTHER THAN THE CONSTRUCTION ACTIVITIES ARE NOT EXPECTED. 2. ILLICIT AND NON STORMWATER DISCHARGES: A. IN ACCORDANCE WITH THE DEP MASSACHUSETTS STORMWATER HANDBOOK, AN ILLICIT DISCHARGE DOES NOT INCLUDE DISCHARGES
- FROM THE FOLLOWING ACTIVITIES OR FACILITIES: FIRE FIGHTING, WATER LINE FLUSHING, LANDSCAPE IRRIGATION, UNCONTAMINATED GROUNDWATER, POTABLE WATER SOURCES, FOUNDATION DRAINS, AIR CONDITIONING CONDENSATION, FOOTING DRAINS, INDIVIDUAL RESIDENT CAR WASHING, FLOWS FROM RIPARIAN HABITATS AND WETLANDS, DECHLORINATED WATER FROM SWIMMING POOLS, WATEF USED FOR STREET WASHING AND WATER USED TO CLEAN RESIDENTIAL BUILDINGS WITHOUT DETERGENTS.
- B. ILLICIT DISCHARGES TO THE STORMWATER MANAGEMENT SYSTEM SHALL BE PROHIBITED. ILLICIT DISCHARGES INCLUDE WASTEWATER DISCHARGES AND DISCHARGES OF STORMWATER CONTAMINATED BY CONTACT WITH PROCESS WASTES, RAW MATERIALS, TOXIC POLLUTANTS, HAZARDOUS SUBSTANCES, OIL, OR GREASE. 3. MAINTENANCE AND CONTROLS:
- A.) DURING CONSTRUCTION, ALL SEDIMENT CONTROL MEASURES SHALL BE MAINTAINED IN EFFECTIVE OPERATING CONDITION, IN THE EVENT THAT THE MEASURES ARE NOT WORKING PROPERLY OR IF ADDITIONAL MEASURES ARE REQUIRED, MAINTENANCE AND ADJUSTMENTS SHALL BE MADE BY THE OPERATOR AS SOON AS POSSIBLE BEFORE THE NEXT RAIN STORM. B.) DURING CONSTRUCTION. IN THE EVENT THAT MAINTENANCE OR IMPLEMENTATION CANNOT BE MADE PRIOR TO THE NEXT RAIN STORM.
- THE SITUATION SHALL BE DOCUMENTED BY THE OPERATOR AND ALTERNATIVE BMP'S IMPLEMENTED AS SOON AS POSSIBLE C.) DURING CONSTRUCTION. CATCH BASINS SUMPS AND SEDIMENT TRAPS SHALL BE CLEANED OF SEDIMENT WHEN THE CAPACITY HAS BEEN REDUCED BY 50%.
- 4. MANAGEMENT PRACTICES: A.) ALL CONTROL MEASURES SHALL BE PROPERLY INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE MANUFACTURE'S RECOMMENDATIONS AND GOOD PRACTICES. INAPPROPRIATE OR INCORRECT USE OF THE CONTROL SHALL BE MODIFIED AS SOON AS PRACTICABLE.
- B.) OFF-SITE ACCUMULATION OF SEDIMENT MUST BE REMOVED IMMEDIATELY. C.) LITTER, CONSTRUCTION DEBRIS, AND CONSTRUCTION CHEMICALS THAT COULD BE EXPOSED TO STORMWATER MUST BE PREVENTED
- FROM BECOMING A POLLUTANT SOURCE IN STORM WATER DISCHARGES. D.) STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS POSSIBLE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN 14 DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS TEMPORARILY OR PERMANENTLY CEASED. ALL AREAS DISTURBED BY CONSTRUCTION SHALL BE STABILIZED PRIOR TO AND
- DURING WINTER CONDITIONS. E.) A VEGETATED BUFFER SHALL BE MAINTAINED WHEREVER POSSIBLE BETWEEN THE WORK AREA AND DOWNSTREAM RESOURCE AREAS AND PROPERTY BOUNDARIES.
- F.) PROVIDE VELOCITY DISSIPATERS OR RIP RAP AT ALL TEMPORARY AND PERMANENT STORMWATER POINT DISCHARGES.



-CLEAN SAND BED

PRIVEWAY

D+2.0'

MISC. UTILITY TRENCH DETAIL

SCALE: NOT TO SCALE

